

01/14/2021

**Requests for Bids  
Wolfeboro NH Department of Public Works  
Solid Waste Compactor**

**Invitation:**

Sealed Bid proposals, plainly marked, "Solid Waste Compactor" on the outside of the envelope addressed to Finance Department, 84 South Main Street, PO Box 629, Wolfeboro, NH 03894, will be accepted until 2:00 PM on Thursday, February 11th, at which time the bids will be opened and read aloud. Questions regarding the bid should be addressed to the Public Works Dept. – Adam Tasker at 603-651-6559.

**Specifications:**

**Wastequip Model 445HD- 4yd Stationary Compactor**

- Tri-Volt/TEFC Motor, UL/CUL Listed, WASTEC Rated, Multicycle Timer, 100% Full Light, ANSI Z.245.2 Compliant, Guardian Control System, NEMA 4 Rated Control Panel, Heavy Duty Ratchet Binders, Override-Packout Hydraulic Pressure Boost, (AMS) Automatic Maintenance Scheduler, Low Temperature oil, Pour point 20° F, Compactor controls in the face of the cabinet,
- **Factory Warranty:** Three (3) Years Structural, One (1) Year Parts and Labor. Painted Dark Green.
- Misc.: Remote 15HP, Tri-volt 208/230/460, Three (3) phase power unit with weather cover to be mounted on the rear of the compactor and wired for 208 volt, Three (3) phase power.
- **Trade-In Used Equipment** Trade-in on the existing Rudco Model RP-400 Compactor and the power unit, "AS-IS".
- Oil heater thermostatically controlled, 10-60 gallon reservoir. - Factory Supplied.
- Controls on 15' remote pendent in lieu of mounting in panel face, Factory option for Stationary & Self-Contained Models. - Factory Supplied.
- Pressure gauge - color coded and numeric - on 15' hose-mounted.
- Guide Rails - 5' standard, available on 145-245-265X & 345. - Factory Supplied.

- **FABRICATION** Relocate both ratchet binders on the compactor, they will need to be 19" to centerline of the ratchet binder bolt from the side of the compactor and moved forward to 2" behind the breaker bar.
- New Ratchet Binder Extensions will need to be built out of 1/2" Plate steel and gusseted back to the side to the compactor. Binder extensions will be installed prior to delivery and install.
- Need to replace the lower 60" of the steel wall due to removal of the old compactor. We will install the new 445HD compactor under the existing hopper system, install then new 60" lower section of the steel wall and will close in the additional 24" x 12' steel wall.
- Town of Wolfeboro, NH will be responsible to remove the existing concrete block wall and dispose of the blocks. Bidder will Install a new Left side wall section up top and flare out the new wall with addition section of Diamond plate to widen out the loading area to the hopper.
- Bidder will need to install a 6" Kick plate at the edge of the hopper loading area, it will include a 1/4" Slope section to allow the skid steer operator push the material into the hopper and not drive into the hopper. This 6" Kick Plate is Required by ANSI & OSHA. It will be painted Safety Yellow.
- **FABRICATION** New Single Swing (left hand Hinge) Safety Gate, Nine (9') Feet wide painted Safety Yellow and will include the Magnetic Interlock Switch to meet ANSI & OSHA Safety.
- Freight charges to Wolfeboro, NH Transfer Station.
- **Installations** Bidder will need to cut out and remove the lower 60" of the existing steel wall, the existing hopper system will be supported and cut off the existing Rudco compactor and we will pull out the old compactor from the building. Will need to clean the area before installing the New Compactor under the hopper system, Hopper will be flashed to the New 445HD Compactor with 7 gauge sheet steel. Once the compactor has been installed into place, will need to anchor the compactor to the concrete floor, install the power unit and wire to the electrical disconnect, mount the controls and the pressure gauge up top.
- Bidder will remove the left side wall and install new diamond plate sections and new wall to increase the loading section to the hopper, install the new safety gate system and wire in the magnetic interlock switch.

Insurance:

Contractors shall procure and maintain for the duration of the contract the following coverage, and shall provide a certificate and endorsement naming the Town of Wolfeboro and its officials, employees and agents as additional insured. This coverage shall be primary in the event there is another insurance applicable. The Town of Wolfeboro must be provided with notice of cancellation of coverage at least 30 days prior to cancellation.

Commercial General Liability	\$1,000,000 per occurrence/\$2,000,000 aggregate
Automobile Liability	\$1,000,000 per accident for bodily injury and
property damage	
Worker's Compensation	As required by NH Statue
Employer's Liability	\$1,000,000 per accident, injury, disease

Bidders shall use the attached bid form.

The Town of Wolfeboro reserves the right to reject any or all bids, to waive technical or legal deficiencies, and to accept any bid that it deems to be in the best interest of the Town.

**01/14/2021**

**Requests for Bids  
Wolfeboro NH Department of Public Works  
Solid Waste Compactor**

**BID PROPOSAL FORM**

Bid Amount as described in the Specifications

\$ \_\_\_\_\_

(Price bid shall be valid through December 31, 2021.)

The undersigned agrees that he/she on behalf of the bidder has read the bid proposal documents, the bid specifications, and agrees to the terms and conditions set forth therein, and has the legal authority to bind the bidder to this bid.

<hr/> Date	<hr/> Bidder – Name of Firm
------------	-----------------------------

<hr/> Phone	<hr/> Name: Printed and signed (Authorized Signature)
-------------	---

<hr/> Fax	<hr/> Title
-----------	-------------

<hr/> E-mail Address	<hr/> Business Address
----------------------	------------------------

	<hr/> City, State, Zip Code
--	-----------------------------